

## **ON-SITE SEWAGE DISPOSAL "AS-BUILT" PLOT PLAN REQUIREMENTS**

An "as-built" should accurately depict the following:

1. Installer's name, address and signature
2. Assessor's Parcel Number
3. Driveway
4. Well
5. House footprint
6. Triangulated measurements from two house corners to both lids of the septic tank and the first "D" box or major component near the leachfield. Include triangulated measurements to the pump tank and sand filter, if present.
7. Accurate measurement of the length of the leach lines and the distance between D-boxes
8. Lot lines
9. Septic tank volume
10. Pump tank volume
11. North arrow